

1 70383

7-31-87

264 R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,143-0000

NE SW SE, SEC. 11, T 19 S, R 26 W/R

990 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5051

Lease Name Antenen Well # 4

Operator: Reed Oil Company  
Name & Address P.O. Box 355  
Great Bend, KS 67530

County Ness 148.62  
Well Total Depth 4573 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 11:33 a.m. Day: 31 Month: 7 Year: 19 87

Plugging proposal received from Howard Cain

(company name) Beredco, Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2577'  
Anhydrite 1855-95'

- 1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1100' with 80 sx cement,
- 3rd plug at 315' with 40 sx cement, 4th plug at 0-40' with 10 sx cement,
- 5th plug to circulate rathole with 10 sx cement,
- 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 2:15 p.m. Day: 31 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1895' with 50 sx cement,

- 2nd plug at 1100' with 80 sx cement,
- 3rd plug at 325' with 40 sx cement,
- 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement,
- 6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
If (info / expenses) observe this plugging.

Signed Dan Gordon (TECHNICIAN)

DATE 8-12-87

INV. NO. ~~17803~~ 17803 SEP 17 1987  
7-31

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date July 22 1987 month day year

API Number 15-135-23,143

OPERATOR: License # 05051

NE SW SE Sec. 11 Twp. 19 S. Rg. 26 West

Name Reed Oil Company

990 Ft. from South Line of Section

Address P.O. Box 355

1650 Ft. from East Line of Section

City/State/Zip Great Bend, Kan 67530

(Note: Locate well on Section Plat on reverse side)

Contact Person Charles W. Steincamp

Phone (316) 793-7456

Nearest lease or unit boundary line 990 feet

CONTRACTOR: License # 5147

County Ness

Name Baredco, Inc.

Lease Name Antenen Well #

City/State Wichita, Kan 67530

Ground surface elevation 2577 feet MSL

Well Drilled For Well Class Type Equipment

Domestic well within 500 feet

X Oil BWD Infield X Mud Rotary

Municipal well within one mile

Gas Inj X Pool Ext Air Rotary

Surface pipe by Alternate

OWWO Expl Wildcat Cable

Depth to bottom of fresh water 120'

If OWWO: old well info as follows:

Depth to bottom of usable water 1000'

Operator

Surface pipe planned to be set 280'

Well Name

Projected Total Depth 4600 feet

Comp Date Old Total Depth

Formation Mississippi Dolomite

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 7/17/87 Signature of Operator or Agent Charles W. Steincamp Title Geologist

For KCC Use: Conductor Pipe Required 200 feet Minimum Surface Pipe Required 100 feet per Alt. 10'

This Authorization Expires 1-20-88 Approved By [Signature] 7-20-87

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

Table with 3 columns: Plug #, Depth (ft), and Material. Includes entries for 1st plug @ 1900', 2nd plug @ 850', 3rd plug @ 310', 4th plug @ 40', 5th plug @ 10', and (2) Rathole with 10'.

Handwritten notes and logs: PUSHER Howard Cain, TD 4573' FORMATION MISS., SURFACE PIPE 8 7/8" @ 295', ANHYDRITE 855-95 ELEVATION 2577, STARTING TIME & DATE 11:33 AM 7-31-87, COMPLETION TIME & DATE 2:15 PM 7-31-87, 1st PLUG @ 1895 FT. W/ 50 SX, 2nd PLUG @ 1100 FT. W/ 80 SX, 3rd PLUG @ 325 FT. W/ 40 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ 10 SX, WATER WELL PLUGGED W/ [unclear], CEMENT COMPANY [unclear], TECHNICIAN G.R. Don Goodrow, 6/14/87 6709d

RECEIVED STATE CORPORATION COMMISSION AUG 10 1987 CONSERVATION DIVISION Wichita, Kansas