

8-2-88

1 051075

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23.202-0000
SE SE SW, SEC. 11, T 19 S, R 26 W/E

330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name _____ Day _____ Well # 1

Operator Name: The Dane G. Hansen Trust

County Ness 149.05

Address P.O. Box 187

Well Total Depth 4586 feet

Logan, KS 67646

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 2 Month: 8 Year: 19 88

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-928-2457

were: 5 1/2" at 4568' Open hole at 4568-86'

1st plug sand back to 4500' and dump 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx

cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 4 1988

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 2 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 5 sx cement on top of

sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2590' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE 8-11-88

Signed Richard W. Lacy
(TECHNICIAN)

INV. NO. 21845