

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23183-00-00
Spot: CSWSWSE Sec/Twnshp/Rge: 11-19S-26W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: ANTENEN Well Number: 1
County: NESS Total Vertical Depth: 4625 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 265 WITH 165 SX CMT
Production: Size 5.5 feet: 4625 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/05/2002 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KCC Phone: (620) 225-8888

Proposed Plugging Method: PUMP 400# HULLS & 40 SX CMT DOWN 5 1/2" & DISPLACED TO 4000'. RUN BOND LOG & DETERMINE BOTTOM OF CMT ON TOP STAGE. PERFORATE BELOW CMT. FILL 5 1/2" FROM PERFORATIONS TO SURFACE WITH CMT. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS WITH CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/05/2002 2:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 4556-4560 & 4576-4578'. PUMPED 400 SX OF HOWCO LITE DOWN 8 5/8" X 5 1/2" ANNULUS. PUMPED 200 SX OF HULLS - 40 SX CMT DISPLACED WITH 60 BBL WATER. MAXIMUM PRESSURE 1100 PSIG. SHUT IN PRESSURE 1000 PSIG. RAN BOND LOG. BOTTOM OF CMT 2050'. PERFORATED @ 1380'. PUMPED 80 SX CMT (20 BBL OF SLURRY) DOWN 5 1/2" CASING. MAXIMUM PRESSURE 1600 PSIG. INITIAL SIP 1500 PSIG. PRESSURE TESTED 8 5/8" X 5 1/2" ANNULUS WITH CMT. MAXIMUM PRESSURE 800 PSIG. INITIAL SIP 800 PSIG. PUMPED NO CMT.

RECEIVED
DEC 10 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% POZMIX BY COPELAND. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

Form 23-23