

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-135-00272-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Ness County. Sec. 31 Twp. 19S Rge. 21 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Parker Petroleum Company, Inc.  
Lease Name Petersillie Well No. 1  
Office Address Box 791 - Ponca City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-13 19 56  
Application for plugging filed 10-13 19 56  
Application for plugging approved 10-13 19 56  
Plugging commenced 10-13 19 56  
Plugging completed 10-13 19 56  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4421 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Toronto	No Show	3777		8 5/8	365'	
Lansing	"	3804				
Base of Kansas City	"	4128				
Upper Marmaton	"	4303				
Cherokee	"	4328				
Mississippi	Slight Show	4368				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with heavy rotary mud to 350'. Halliburton plug set - cemented with 20 sacks cement - Top plug set at 45' and cemented with 15 sacks cement. Cement to top of hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. C. Smitherman Drilling Company  
Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Joe W. Cain (employee of owner) or (~~owner~~/~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain  
Box 627 - Augusta, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 56

My commission expires October 23, 1958.

Kath H. Carter  
Notary Public.  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 31 T. 19 R. 21W  
BOOK PAGE 107 LINE 26

OCT 19 1956  
10-19-56  
CONSERVATION DIVISION  
Wichita, Kansas

15-135-00272-00-00

PETERSILLIE #1

Company - Parker Petroleum Co., Inc.  
 Contractor - L. C. Smitherman Drlg. Co.  
 Commenced - 9-27-56  
 Completed - 10-13-56  
 Total Depth - 4421'  
 Initial Prod. - D & A

Location: NB NE SE, Sec. 31-19S-21W,  
 Ness County, Kansas.  
 Elevation: 2258 GL  
 Casing: 8 5/8" - 365' cemented W/350 Sks.

Figures Indicate Bottoms of Formations:

Depth	Formation
0 - 45	Clay & Sand
45 - 365	Shale & Lime
365 - 1000	Shale - Red Bed W/Lime Strks.
1000 - 1150	Sand
1150 - 1350	Shale W/Sand Strks.
1350 - 1475	Shale & Lime Shells
1475 - 1521	Lime & Shale
1521 - 1659	Shale
1659 - 2290	Shale & Lime
2290 - 2312	Lime
2312 - 2475	Shale & Lime
2475 - 2591	Lime W/Shale
2591 - 2620	Shale & Lime
2620 - 2755	Lime
2755 - 2803	Lime & Shale
2803 - 2860	Broken Lime
2860 - 3073	Lime & Shale
3073 - 3120	Lime
3120 - 3225	Shale & Shells
3225 - 3300	Shale - Sticky
3300 - 3420	Shale & Lime
3420 - 3475	Lime
3475 - 3525	Shale & Shells
3525 - 3575	Lime W/Shale Strks.
3575 - 3763	Lime
3763 - 3863	Sand & Shale W/Lime
3863 - 4165	Lime - K.C.
4165 - 4280	Lime W/Shale Brks.
4280 - 4312	Shale W/Sand Strks. (Cherokee)
4312 - 4327	Sand
4327 - 4376	Shale & Lime
4376 - 4421	Lime (Mississippi)
4421 - R. T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Petersillie #1, located in the NB NE SE, Section 31-19S-21W, Ness County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

*L. C. Smitherman*  
 \_\_\_\_\_

Subscribed and sworn to before me this 17th day of October, 1956.

*W. L. Carter*  
 \_\_\_\_\_  
 Notary Public

My commission expires October 23, 1958.

**PLUGGING**  
 FILE SEC 31 T 19 R 21W  
 BOOK PAGE 107 LINE 24

RECEIVED  
 OCT 19 1956  
 10-19-1956