

15-135-30025-00-00

LEASE NAME Foos "A-P"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Ritchie Exploration, Inc.

SEC. 31 TWP. 19 RGE. 21W (E) or (W)

ADDRESS 125 N. Market #1000 Wichita, KS 67202

COUNTY Ness

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed

Character of Well Oil

Plugging Commenced 3-19-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3-20-97

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 428'

Show depth and thickness of all water, oil and gas formations.

03-27-1997

RECEIVED
KANSAS CORP COM
MAR 27 11:40 AM '97

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	512'	none
				4 1/2	4405'	1520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s' Plugged off bottom with sand to 4360' & ran 4 sks cement. Shot casing at 1520', came loose. Pulled one it. to 1490', pumped 50 sks w/100# hulls at 1490'. Pulled csg to 700', pumped 40 sks w/100# hulls. Pulled to 512', pumped 50 sks cement. Pulled to 200', pumped 40 sks cement. Pulled to 40', pumped 10 sks cement. Pulled rest of csg. Plugging complete. 60/40 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 25th day of March, 19 97

Jane Serberg
Notary Public

My Commission Expires:

