


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 31 Twp. 19 Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Pickrell Drilling Company
Lease Name Schaben "A" Well No. 2
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed FEBRUARY January 6, 19 65
Application for plugging filed FEBRUARY January 6, 19 65
Application for plugging approved FEBRUARY January 6, 19 65
Plugging commenced FEBRUARY January 6, 19 65
Plugging completed FEBRUARY January 6, 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4473 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	385'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 270', set plug, cemented with
20 sacks. Heavy mud to 40', set plug,
cemented with 10 sacks cement to bottom
of cellar. Plugged rat hole with 2 sacks
cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1965
02-10-1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.


C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of February, 1965

Maxine Blackman
Maxine Blackman, Notary Public.

My commission expires June 21, 1966



15-135-30015-00-00

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 1-25-65

Rotary Drilling Completed 2--5-65

LOCATION: Schaben "A" No. 2, C SE NW Section 31-19-21W, Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (18 jts) 8 5/8" surface casing set at 384' cemented with 180 sacks cement. Circulated. Completed 8:15 P.M. January 25, 1965. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

165	Clay & Shale	<u>C. F. S.</u>
385	Shale & Sand Streaks	4365
1455	Shale & Shells	4415
1535	Shale & Lime	4423
1575	Lime	4430
1770	Shale & Lime	4433
2215	Shale & Shells	4438
2530	Lime & Shale	4443
2707	Lime	4473
2820	Lime & Shale	
3060	Lime	
3815	Lime & Shale	<u>Slope Tests</u>
3889	Lime	2500
4005	Lime & Shale	3025
4135	Lime	3570
4220	Lime & Shale	4315
4430	Lime	
4473	Mississippian + RTD	<u>S. L. M.</u>
		3675
		4010
		4326

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1965
02-10-1965
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 8th day of February, 1965, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public