

STATE OF KANSAS
TATE CORPORATION COMMISSION
30 S. Market, Room 2070
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-135-21,845-00-01

LEASE NAME Lyle Schaben

WELL NUMBER "P" #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2030 Ft. from N Section Line

710 Ft. from E. Section Line

SEC. 32 TWP. 19 RGE. 21W (E) or (W)

COUNTY Ness

LEASE OPERATOR RITCHIE EXPLORATION, INC.

ADDRESS P.O. Box 783188 Wichita, Kansas 67278-3188

PHONE (316) 691-9500 OPERATORS LICENSE NO. 4767

Date Well Completed _____

Plugging Commenced 2-22-02

Plugging Completed 2-27-02

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.O. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	505'	None
				5-1/2"	4390'	835'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Plugged off bottom with sand to 4267' and 5 sacks cement. Shot pipe @2507', pipe parted @835', pulled 20 its. of 5-1/2". Ran 2-7/8" tubing to 925', pumped 400# hulls and 80 sacks cement, pulled up to 525', pumped 50 sacks cement, pulled up to 40' and circulated 10 sacks cement to surface 60/40-pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of February, 2002

Irene Herzberg
Notary Public

My Commission Expires:

