

STATE OF KANSAS
STATE CORPORATION COMMISSION
207 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-19003-00-01

LEASE NAME Moore CP

WELL NUMBER 2

3300 Ft. from 3N Section Line

4770 Ft. from E. Section Line

SEC. 30 TWP. 19S RGE. 21W (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 9-30-02

Plugging Completed 10-2-02

RECEIVED
10-22-2002
OCT 22 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR RITCHIE EXPLORATION, INC.

ADDRESS P.O. Box 783188

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Richard Lacey (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4425'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	508'	None
				4-1/2"	4424'	922'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3800' and 4 sacks cement. Shot pipe @922', pulled up to 730', pumped 10 sacks gel and 50 sacks cement, pulled up to 530', pumped 50 sacks cement, pulled up to 40' and topped off with 25 sacks cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances stated herein, and that the statements, and matters herein contained and the log of the above-described well as filed therewith, are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18th day of October 2002

[Signature]
Notary Public

My Commission Expires: _____



OK