

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name L. J. Dreiling & Sons, Inc.

Complete Address Victoria, Kansas

Lease Name Evergreen Enterprises Well-No. 1

Location SE SE NW Sec. 30 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 1.15A Day 1 Month 12 Year 1969

The above well was plugged as follows:

RTD 3750' 8 5/8 csg set at 190' cwc 125 sk Gmt. Mat. 50-50 poz cmt 6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 12/3/69

INV. NO. 972-11