

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

5-18

FILE NO. 5-8

LOCATION SW SW NE

SEC. 17 TWP. 11 RGE. 19W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 22 Lease Giinther

Operator N C R A Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3629 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 245' circulated with cement - 5 1/2" 3627' with 150 sax cement behind - Perforated at 3439'.

Filled with sand to 3430', set 4 sax cement with dump bailer, pulled 2125' 5 1/2" - pumped hole full commercial mud (20 sax)

pumped cementing plug to ~~34~~ 445' followed by 148 sax cement.

Cement 445' to 0' - Cementing by Halliburton Co.

**PLUGGING**  
FILE SEC 17 T 11 R 19W  
BOOK PAGE 5 LINE 18

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 7 1954  
02-03-54  
CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent  
Date 2-1-54