

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051 - 22,928-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Montgomery Exploration, Inc.

Complete Address P.O. Box 1114, Hays, Ks. 67601

Lease Name Gillbert

Well No. 1

Location NW SE NE

Sec. 17 Twp. 11 Rge. 19 (East) (West)

County Ellis

Total Depth 3590'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor Montgomery Exploration, Inc.

Address P.O. Box 1114, Hays, Ks. 67601

License No. _____

Operation Completed: Hour: 11:45 PM Day: 30 Month: 3 Year: 19 82

Plugging Operations attended by Agent?: All xxx Part _____ None _____

The above well was plugged as follows:

8 5/8"-220' S.P. cuc. w/155 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug w/10

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 220' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 220' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 4-6-82
INV. NO. 9855-W

116.68

Signed: _____
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

APR - 5 1982

CONSERVATION DIVISION
Wichita, Kansas

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 200 Colorado, Derby Bldg.
 Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

April 6, 1982

INVOICE NUMBER: 9855-W

TO: Montgomery Exploration, Inc.

Box 1114

Hays Kansas 67601

PLUGGING ASSESSMENT AS FOLLOWS: **PAYABLE UPON RECEIPT**

Gilbert #1

NW SE NE Sec. 17-11-19W

Ellis

3590'

\$116.68

NOTE: We also need the following before our file is completed:


- X _____ Well Plugging Record (CP-4)
 X _____ Well Log
 X _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



 Administrator

Mr. Gilbert Scheck 2202 Canterbury Rd., Hays Ks. 67601 (913) 628-2600

is hereby assigned to supervise the plugging of the above mentioned well.