

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

1505120970.0000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Center, Wichita, Kansas

Lease Name Zerfas Well No. 2

Location NW NE SE Sec. 30 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3781'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 7 P Day 27 Month 7 Year 1974

The above well was plugged as follows:

RTD 3781' 8 5/8 csg set at 171' cwc 150 sk. Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, displaced 70 sk cmt at 650' thru drill pipe.

Heavy mud to 185' set cementing plug & displaced 20 sk cmt thru drill pipe. Heavy

mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/31/74

INV. NO. 9640-W