

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name T. L. Ferrier

Complete Address: 300 Schweiter Bldg., Wichita, Kansas

Lease Name Metz Well No. 1

Location C N/2 S/2 SW Sec. 13 Twp. 11 Rge. 19 (E) (W) X

County Ellis Total Depth 3478'

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Dunne-Gardner Drlg. Co. Inc.,

Address: Wichita, Kansas License No. 526

Operation Completed: Hour 11: P Day 12 Month 10 Year 1966

The Above well was plugged as follows:

Total Depth 3478' 8 5/8 csg set at 175' cwc 135 sc.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 30 sc

cement thru drill pipe. Heavy mud to 170' set cementing plug and displaced 20 sc.

cement thru drill pipe. Heavy mud to 40' set cementing plug. 1/3 sc hulls and 8 sc.

cement to base of cellar. Plugged rat hole with 2 sc. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey  
Well Plugging Supervisor

DATE 10/14/66

INV. NO. 4099-W