

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Clinton Oil Company  
Complete Address Box 1201 Wichita, Kansas 67201  
Lease Name H. W. Vine Well No. 3  
Location NW NW SW Sec. 14 Twp. 11 Rge. (E) (W) 19  
County Ellis Total Depth 3497'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Kelso Pipe Pulling  
Address Box 176 Chase, Kansas 67524 License No. 683  
Operation Completed: Hour 3 P Day 9 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3497' 8 5/8 csg set at 1279' cwc 575 sk.  
5 1/2 csg set at 3485' cw 200 sk cmt.  
Filled 5 1/2 csg with sand (3497-3450) dumped 4 sk cmt W/dump bailer. (3450-3420)  
Cutoff and recovered 81 jts (1695') of 5 1/2 csg.  
Filled 8 5/8 csg with mud to 490' -set rock & sand bridge (490-475)  
Filled with readymix cement from 475 to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray  
Well Plugging Supervisor

DATE 7/11/74  
INV. NO. 9494W