

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 44-14

LOCATION SE SE SW

SEC. 14 TWP. 11 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease ~~Trans Era Pet~~ Vine

Operator Trans Era Pet Address 420 W Douglas

Field _____ County Ellis

Total Depth 3470 Feet.

Plugging Contractor Miller Casing Pulling

Plugging Contractor's License No. 12

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1286' circulated with cement - 5 1/2" at 3467' with
50 sax cement behind.

Filled with chat to 3450', set 4 sax cement with dump bailer,
pulled 3018' 5 1/2" -pumped hole full mud (35 sax commercial mud)
pumped cementing plug to 225' followed by 75 sax cement -
Cement 225' to 0'.

Mudding and cementing by Sun cementing Co.

Edon Petty

District Conservation Agent

Date 3-17-56

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1956
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC. 14 T. 11 R. 19
BOOK PAGE 44 LINE 14