

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 103-45

Approx SE SW NW
LOCATION _____

SEC. 14 TWP. 11 RGE. 19

Dry Hole _____ Abandoned Oil Well X _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Vine

Operator Don Pratt Oil Co Address Hays, Kans

Field _____ County Ellis

Total Depth 3524 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 1309' circulated with cement - ~~5 1/2~~ 5 9/16" at

3522' with 100 sax cement behind.

Set 5 sax cement on bottom with dump bailer - pulled 2600'

5 9/16" - pumped hole full commercial mud - pumped cementing

plug to 280' followed by 90 sax Pozmix cement - cement 280' to 0'.

Cementing by Halliburton Co. 600# maximum pump pressure.

Edson L...
District Conservation Agent

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1955
03-22-55
CONSERVATION DIVISION
WICHITA, KANSAS

DATE 3-18-55

PLUGGING
FILE SEC 14 T 11 R 19W
BOOK PAGE 103 LINE 45