

10-20-F7

To: 1 070450
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22.455 0000
NW NW NE, SEC. 6, T 25 S, R 15 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541
Operator: Petex, Inc.
Name &
Address Routee 2, Box 553
Rogersville, MO 65742

4950 feet from S section line
2310 feet from E section line
Lease Name Aiken Well # 1
County Stafford 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling License Number 5104
Address Box 1413, Suite 2C, Great Bend, KS 67530

Company to plug at: Hour: 8 a.m. Day: 20 Month: 10 Year: 19 87

Plugging proposal received from George Miller
(company name) Blue Goose Drilling (phone) 316-792-5633
Elevation 2050'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1006-18'
1st plug at 1018' with 50 sx cement,
2nd plug at 290' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 10 a.m. Day: 20 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1018' with 50 sx cement,
2nd plug at 290' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-28-87

INV. NO. 18689

OCT 26 1987

Signed Dan Goodrow
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

10-20 DEC 03 1987

FORM CP-2/3
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date September 10, 1987 month day year

API Number 15-185-22,455-0002 NW NW NE Sec. 6 Twp. 25S, Rg. 15 East 4950 West 2310 Ft. from South Line of Section Ft. from East Line of Section

OPERATOR: License # 8541 PELEX, Inc. Name Address Route 2, Box 553 City/State/Zip Rogersville, MO 65742 Contact Person Larry Childress Phone (417) 887-6289 5104

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County Stafford

CONTRACTOR: License # Blue Goose Drilling Name City/State Great Bend, KS

Lease Name Aiken Well # 1 Ground surface elevation 2050 feet MSL

Well Drilled For: Well Class: Type Equipment: Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 180' Depth to bottom of usable water 200'

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1 2X Surface pipe planned to be set 220' Conductor pipe required Projected Total Depth 4400 feet Formation Miss

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 8/18/87 Signature of Operator or Agent Larry Childress Title President

For KCC Use: Conductor Pipe Required feet: Minimum Surface Pipe Required 220 feet per Alt. 1 This Authorization Expires 2-24-88 Approved By G.H. 8-24-87

Spud 10-12-87

240 + of 8 5/8"

Yes WW

D.G. NW NW NE Sec. 6 Twp. 25S, Rg. 15 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, formation, and material. Includes entries for Rathole and Mousehole.

Vertical list of well parameters: PUSHER George Miller, TD 4550 FORMATION Arb., SURFACE PIPE 8 5/8" @ 263', ANHYDRITE 1018' ELEVATION 2050', STARTING TIME & DATE 8:00 10-20-87, COMPLETION TIME & DATE 10:00 10-20-87, 1st PLUG @ 1018 FT. W/ 50 SX, 2nd PLUG @ 290 FT. W/ 40 SX, 3rd PLUG @ 40 FT. W/ 10 SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ 10 SX, CEMENT COMPANY B.J. Titan

TECHNICIAN D.G. RECEIVED STATE CORPORATION COMMISSION OCT 26 1987 CONSERVATION DIVISION Wichita, Kansas