

1 060656

API NUMBER 15- 135-22,872-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NW NW , SEC. 29 , T 18 S, R 25 W/K  
4950 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177

Lease Name Johnson 'A' Well # 1  
County Ness 144.89

Operator: Foxfire Exploration, Inc.  
Name & Address 1022 Union Center  
Wichita, KS 67202

Well Total Depth 4458 Mississippi feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Foxfire Drilling, Co., Inc. License Number 8430  
Address P. O. Box 133, WaKeeney, KS 67672

Company to plug at: Hour: 2:00 pm Day: 3 Month: September Year: 19 85

Plugging proposal received from Gary Fisher  
(company name) Foxfire (phone) 316-265-6296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1744-82  
Elevation 2471 KB

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' out of the base of the Cheyenne with 80 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement  
solid bridge

4th & 5th plugs hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with  
10 sx cement Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 4:30 pm Day: 3 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1780' with 50 sx cement, 2nd plug at 1010' with 80  
sx cement, 3rd plug at 260' with 40 sx cement, 4th & 5th plugs - solid bridge-- hulls -  
plug at 40' -- cement to surface with 10 sx cement. 6th plug to circulate rat hole with  
10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE SEP 17 1985

Signed Paul A. Luthi / rjl (TECHNICIAN)

INV. NO. 10116

SEP 16 1985 09-16-1985 CONSERVATION DIVISION Wichita, Kansas

9-3 OCT 0 8 1985