

1060170

TO: STATE CORPORATION COMMISSION

8-23

API NUMBER ^{23,} 15-135-~~90~~773-00-00
NW NW SE SEC. 34, T 18 S, R 25 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SPRUILL E WELL # A-1

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS 143.14

OPERATOR LICENSE # 5011

WELL TOTAL DEPTH 4405 FEET

OPERATOR: VIKING RESOURCES, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4398' WITH 165 SX

NAME AND ADDRESS 105 S BROADWAY, SUITE 1040 SURFACE CASING: SIZE 8 5/8" @ 226' WITH 140 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 9:10 AM DAY: 23 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: OPEN HOLE Backside circulated w/ 250 sx cement held at 750 psi.

BOTTOM PLUG PUMP 50 SX CEMENT WITH 300# HULLS. GEL SPACER TO ANHYDRITE THEN 110 SX CEMENT
PRESSURED TO 2000#. SHUT IN WITH 1400#. WENT DOWN BACKSIDE WITH 15 SX CEMENT.
PRESSURED TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 23 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMP 50 SX CEMENT WITH 300# HULLS. GEL SPACER TO ANHYDRITE THEN 110 SX
CEMENT. PRESSURED TO 2000#. SHUT IN WITH 1400#. WENT DOWN BACKSIDE WITH 15 SX CEMENT.
PRESSURED TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

STATE CORPORATION COMMISSION
SEP - 2 1999
09-02-1999
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I (DID) OBSERVE THIS PLUGGING.

DATE 9-16-99

SIGNED Michael Maier (TECHNICIAN)

FORM CP-2/3

INV. NO. 60538