

1050371

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,674-00-00

SW NE NW, SEC. 35, T 18 S, R 25 WXX  
4220 feet from ~~XXX~~ section line  
3630 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Miner Well # 1

Operator: Viking Resources

County Ness

Name & Address 217 E. William

Well Total Depth 4453 141.72 feet

Wichita, KS 67202-4005

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 7:30 am Day: 29 Month: October Year: 19 84

Plugging proposal received from Mike Sharp

(company name) White & Ellis (phone) 316-692-2424

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1710' with 50 sx cement

2nd plug at 840' with 50 sx cement

3rd plug at 300' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement  
Plugging Proposal Received by Richard W. Lacy (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:45 am Day: 29 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1710' with 50 sx cement, 2nd plug at 840' with 50 sx cement, 3rd plug at 300' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement. 6th plug to circulate rat hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
10-31-1984  
OCT 31 1984

Steve Durrant gave the plugging orders

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED (copy) did not observe this plugging.

DATE 11-7-84

Signed Richard W. Lacy (TECHNICIAN)

INV. NO. 4695

10-29