

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,187-00-00
CSW, Sec. 25, T 18 S, R 25 W

_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5729

Lease Name Sutton Well # 1
(muddy sheets + Dollar Baths)
County Ness

Operator: DYNAMAR ENERGY, Inc
Name & Address 4005 E. KELLOGG
WICHITA, KS 67218

Well Total Depth 4510 feet # 146.58
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 7/8 feet 709'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. FOWLER, MEDICINE LODGE, KS 67104

Company to plug at: Hour: 12 Noon Day: 7 Month: Dec Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Elmo Morganstern

(company name) Clarke (phone) _____

were: Sand bottom to 4317 w/5 qt cmt. Rec. of 2968'
of 5 1/2. Use 50/50 Pozmix, 4% gel-3% CC. Pump the
following sequence: 3 qt. hulls, 20 qt. gel, 70 qt.
cmt., 1 qt. hulls, 15 qt. gel, release 8 5/8" plug and
finish with 100 qt. cmt.

Signed R. Brackman
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 7 Month: Dec Year: 19 82

ACTUAL PLUGGING REPORT Plugged as ordered.
Cementing by Sun.

Remarks: 5 1/2 @ 4508' - perf @ 4474-79
May, pressure 700# - shut in 500#

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1982
12-14-1982
CONSERVATION DIVISION
Wichita, Kansas

Signed R. Brackman
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 4-4-83

INV. NO. 3870-11