

9-13

1 070592

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,690-00-00

S/2 SW SW, SEC. 25, T 18 S, R 25 W/E

330 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3567

Lease Name Sutton Well # 1-25

Operator: Totten Resources, Inc.

County Ness 147.10

Name & Address 2506 Greenleaf Court

Well Total Depth 4526 feet

Wichita, KS 67226

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 611

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Totten Resource, Inc. License Number 3567

Address 2506 Greenleaf Court, Wichita, KS 67226

Company to plug at: Hour: 10:15 a.m. Day: 13 Month: 9 Year: 19 88

Plugging proposal received from Dean Ives

(company name) Totten Resource, Inc. (phone) 913-625-7773

were: 5 1/2" at 4543' PBD 4500' Perfs at 4410-15'

1st plug pump 3 sx hulls, 185 sx Thrifty Mix cement down 5 1/2",

2nd plug pump 15 sx Thrifty Mix, 150 lbs. hulls in first part of 80 sx Thrifty Mix down 8 5/8".

RECEIVED
STATE CORPORATION COMMISSION
09-28-1988
SEP 22 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 13 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 185 sx Thrifty Mix cement down 5 1/2". Maximum pressure 1000 psi and shut in 900 psi.

2nd plug pumped 15 sx Thrifty Mix, then 150 lbs. hulls in first part of 80 sx Thrifty Mix cement down 8 5/8". Maximum pressure 850 psi and shut in 650 psi.

Remarks: Used Thrifty Mix by B.J. Titan. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED (If desired, observe this plugging.)

Signed Dan Goodrow (TECHNICIAN)

DATE 10-6-88

INV. NO. 22536

9-13 NOV 15 1988