

To: 1 060739
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22, 964-00-00

CSENE, SEC. 27, T 18 S, R 25 W10

TECHNICIAN'S PLUGGING REPORT

3300 feet from S section line

660 feet from E section line

Operator License # 5046

Lease Name Dunger Well # 1

Operator: Raymond Oil Co. Inc.

County Ness 145.28

Name & Address P.O. Box 48788

Well Total Depth 4470 Miss feet

Wichita, Kansas
67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A ☒

Other well as hereinafter indicated anhydrite base 1741' Elevation 2430'

Plugging Contractor Duke Drilling Co. Inc. License Number 5929

Address Wichita, Kansas 67202

Company to plug at: Hour: 11:00 AM Day: 25 Month: November Year: 1985

Plugging proposal received from Bill Draney

(company name) Duke Drilling Co. Inc. (phone) 316-792-1074

were: 1st plug @ base of anhydrite w/ 50 sbx cement.

2nd plug @ base of Cheyenne w/ 80 sbx cement.

3rd plug @ 30' below base of surface casing

4th 40' to 0' w/ solid bridge w/ 10 sbx cement.

5th Circulate 15 sbx cement in rat hole

Bob Tarbutton gave the Plugging Proposal Received by Bob Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None ☒

Operations Completed: Hour: 2:30 PM Day: 25 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of heavy mud before spotting

plugs through drill pipe. 1st plug @ 1750' w/ 50 sbx
cement. 2nd plug @ 880' w/ 100 sbx cement. 3rd plug @
240' w/ 40 sbx cement. 4th plug @ 40' on solid bridge w/ wood
plug & 10 sbx cement, filling hole to 0'. 5th plug circulated
15 sbx cement in rat hole through 1 joint of drill pipe.

Remarks Allied pumped 60/40 poss mix w/ 6" to 8" gel.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 10 1985

INV. NO. 11374

DEC 2 1985
12-02-1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthie
(TECHNICIAN)