

1 070120

API NUMBER 15- 135-21,178-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SW , SEC. 17 , T 18 S, R 23 (W)E

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Keller Well # 2

Operator: Mull Drilling Co., Inc.

County Ness 142.25

Name &

Address P. O. Box 2758,

Well Total Depth 4377 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 406

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:15 pm Day: 8 Month: January Year: 19 86

Plugging proposal received from Danny Kilgore

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4365' PBD 4320' Perfs at 4120-48'

1st plug pump 1 sack hulls and 25 sx cement to bottom

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 pm Day: 8 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and 1 sack hulls to bottom, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

Maximum pressure 300 psi and shut in 100 psi

Remarks: Recovered 1230' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986

INV. NO. 12042

JAN 18 1986
01-13-1986
CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Johnson (TECHNICIAN)