

1010149

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,629-00-00

C SE NE, SEC. 19, T 18 S, R 23  
N SE Corner of  
3330 feet from ~~XXX~~ section line  
W SE Corner of  
660 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Bondurant Well # 1-G

Operator: Pickrell Drilling Company

County Ness

Name & Address 110 North Market, Suite 205

Well Total Depth 4343 141.15 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 540

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 North Market, Suite 205, Wichita, KS 67202

Company to plug at: Hour: 5:00 am Day: 6 Month: August Year: 1984

Plugging proposal received from Herb French

(company name) Pickrell (phone) 316-262-8427

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1565' with 50 sx cement

2nd plug at 850' with 40 sx cement

3rd plug at 560' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement  
Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 am Day: 6 Month: August Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1565' with 50 sx cement, 2nd plug at 850' with 40 sx cement, 3rd plug at 560' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
08-10-1984  
AUG 10 1984

Remarks: Used 60/40 Pozmix 22% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)  
Wichita, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
I did not observe this plugging.

Signed Ken Beaker (TECHNICIAN)

DATE 8-14-84

INV. NO. 3079