



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Neal Daniel of Duke Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: National Development Company

Complete Address: 833 N. Waco, Wichita, Ks. 67203

Lease Name: Frisbie Well No. #1

Location: NW SE NW Sec. 19 Twp. 11 Rge. 18 (E) (W)

County: Ellis Total Depth: 3585'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Daniel was instructed to plug the well as follows:

8 5/8"-258' s.p. cuc. w/160 sacks 60/40 posmix-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' w/70 sacks of cement

2nd plug @ 270' w/40 sacks of cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement

Circulate with 10 sacks of cement in rat hole.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

JUN - 2 1982

[Signature]
Conservation Division Agent
Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas