



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1971

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cloer of Champlin Petr. Co. has this
date requested permission to plug the following described well:

Mr. Cloer guarantees payment of the plugging fee.

Operator's full Name: Champlin Petroleum Co.

Complete Address: Box 308 Ellinwood, Ks.

Lease Name: Johnson"L" Well No. 4

Location: 660' FEL & 2310' FSL Sec. 32 Twp. 11 Rge. (E)(W) 18

County: Ellis Total Depth 3670' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cloer was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Muesel
Conservation Division Agent