



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Morgan of Champlin Petr. has this

date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Champlin Petr. Co.

Complete Address: Box 308 Ellinwood, Ks.

Lease Name: Johnson "L" Well No. 1

Location: C S/2 NE SE Sec. 32 Twp. 11 Rge. (E)(W) 18

County: Ellis Total Depth 3300' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Morgan was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 660' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey  
Conservation Division Agent