

State of Kansas



FORM CP-2

15-051-22928-0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Leroy Hunt of Montgomery Exploration, Inc. has this

date requested permission to plug the following described well:

Operator's Full Name: Montgomery Exploration, Inc.

Complete Address: P.O. Box 1114, Hays, Ks. 67601

Lease Name: Gillbert Well No. 1

Location: NW SE NE Sec. 17 Twp. 11 Rge. 19 (E) (W)

County: Ellis Total Depth: 3590'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereafter indicated: _____

Mr. Hunt was instructed to plug the well as follows:

8 5/8"-220' S.P. cuc. w/155 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 220' w/40 sacks cement

3rd plug -solid bridge of hulls & plug @ 40' w/10 sacks cement

Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent
Wichita Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR - 5 1992