

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-20945-00-00
Spot: NESENW Sec/Twnshp/Rge: 16-29S-6E
3754 feet from S Section Line, 2941 feet from E Section Line
Lease Name: WOODS BROTHERS A Well #: 6
County: BUTLER Total Vertical Depth: 2868 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2860	1393	150 SX
SURF	8.625	200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2012 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JAMES R. BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: ACCORDING TO KCC RULES & REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/26/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2755', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 1393', LAYED DOWN 43 JOINGS 4-1/2" CASING (1393'). RIH W/4-1/2" BAILOR, BAILED HOLE DRY @ 250', CMC DUMPED 4 1/2 YARD SLURRY LESS 10% SAND TO SURFACE. (97-3/4 SXS) PLUG DOWN 7-26-2012, 5:00PM. CMC CEMENT TICKET #4030324.

Perfs:

Top	Bot	Thru	Comments
2816	2824	CSG	
2808	2812	CSG	

RECEIVED
AUG 14 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
8/28/12
(TECHNICIAN)