

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-30382-00-00
Spot: NENESW Sec/Twnshp/Rge: 36-31S-4E
2345 feet from S Section Line, 2993 feet from E Section Line
Lease Name: HOLT Well #: 4
County: COWLEY Total Vertical Depth: 2400 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2398	1050	125 SX
SURF	8.625	180		150 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/25/2012 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: KURTIS KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 938-2534

Proposed Plugging Method: PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 07/25/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2300', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1050', LAYED DOWN 25 JTS 5.5" CASING, (1050'). RIH W/TBG @ 252', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7/25/2012. COPELAND CEMENT TICKET #39911.

Perfs:

Top	Bot	Thru	Comments
2350	2352	CSG	

RECEIVED
AUG 15 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

8/28/12
(TECHNICIAN)