

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24307-00-00
Spot: SWNWNESW Sec/Twnshp/Rge: 36-31S-4E
2109 feet from S Section Line, 3898 feet from E Section Line
Lease Name: HOLT Well #: 8
County: COWLEY Total Vertical Depth: 3035 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2450		
CIBP	4.5	2960		
PROD	4.5	3036	1050	210 SX
SURF	8.625	202		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2012 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: KURTIS KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 938-2534

Proposed Plugging Method: PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 07/25/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2200', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 1050', LAYED DOWN 25 JTS 4.5" CASING, (1050'). RIH W/TBG @ 252', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7/25/2012. COPELAND CEMENT TICKET #39910.

Perfs:

Top	Bot	Thru	Comments
2990	2992	CSG	MISS
2478	2481	CSG	KC
2274	2284	CSG	LAYTON SAND

RECEIVED
AUG 15 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
8/28/12 (TECHNICIAN)