

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23456-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 36-31S-4E  
3655 feet from S Section Line, 3655 feet from E Section Line  
Lease Name: HOLT B Well #: 3  
County: COWLEY Total Vertical Depth: 3060 feet

Operator License No.: 34320  
Op Name: LASSO ENERGY LLC  
Address: PO BOX 465  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2427	1250	125 SX
SURF	8.625	210		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/30/2012 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: KURTIS KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 938-2534

Proposed Plugging Method: PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/30/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2250', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1250', LAYED DOWN 38 JTS 5.5" CASING, (1250') RIH W/TBG @ 265', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7/30/2012. COPELAND CEMENT TICKET #38036.

Perfs:

Top	Bot	Thru	Comments
2332	2338	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

[Signature]  
8/28/12 (TECHNICIAN)

RECEIVED  
AUG 15 2012  
KCC WICHITA