

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10370-00-01
Spot: NE Sec/Twnshp/Rge: 31-33S-42W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: STUCKEY Well #: 1-31
County: MORTON Total Vertical Depth: 4220 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN LLC
Address: 15 E 5TH ST STE 3200
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2635		
PROD	5.5	4214	733	WITH 375 SX CMT
SURF	8.625	604		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/07/2012 2:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 2635'. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 610' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 08/08/2012 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 2635'. CASING LEAKS AT 1531' TO 1657' SQUEEZED WITH 177 SX CMT. 1ST PLUG AT 1500' WITH 25 SX CMT. 2ND PLUG AT 610' WITH 50 SX CMT. 3RD PLUG AT 40'-0' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4172	4180		
4158	4164		
4126	4130		
3851	3855		
3774	3780		
3590	3594		
3464	3469		
3348	3359		
3163	3194		
3014	3028		
2896	2902		
2686	2878		

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

RECEIVED
AUG 16 2012

KCC WICHITA

District: 01

Signed Michael Maier
8/28/12 (TECHNICIAN)

RECEIVED
AUG 10 2012
KCC DODGE CITY

AMY