

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22469-00-00
Spot: SWNWSENE Sec/Twnshp/Rge: 20-19S-9W
3304 feet from S Section Line, 992 feet from E Section Line
Lease Name: HABIGER C Well #: 3
County: RICE Total Vertical Depth: 3273 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3249		
PROD	5.5	3251	2200	100 SX
SURF	8.625	250		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2012 1:00 PM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK Witness Type: NONE
Date/Time Plugging Completed: 08/10/2012 2:30 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

SANDED PERFS AT 3190' WITH A 5 SX PLUG OF 60/40 4%. CUT CASING AT 2200'
PULLED UP TO 1261' SET A 35 SX PLUG. PULLED UP TO 859' SET A 35 SX PLUG,
AND PULLED UP TO 325' CIRCULATED WATER THEN PUMPED 105 SX OF 60/40 4%.

Perfs:

Top	Bot	Thru	Comments
3240	3248	CSG	

RECEIVED
AUG 16 2012
KCC WICHITA

Remarks: COPELAND TICKET #339980

Plugged through: CSG

District: 02

Signed

[Signature]
8/28/12 (TECHNICIAN)