

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00775-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 11-30S-8W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SAVAGE GAS UNIT Well #: 1
County: KINGMAN Total Vertical Depth: 4561 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		
PROD 5		4336	750	125 SX
SURF	8.625	202		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/12/2012 4:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RANDY DICK Company: LINN Phone: (620) 425-1000

Proposed Plugging Method: AS PER KCC REQUIREMENTS.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/12/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4100' CAPPED WITH 2SX CEMENT ON TOP. PERF CASING AT 1250'
SPOTTED 35 SX CEMENT THRU; TUBING. PULLED CASING PIPE OFF @ 750'
SPOTTED 35 SX CEMENT. PULLED CASING TO 289' CIRCULATED TO SURFACE
WITH 175 SX CEMENT WITH 3% CC.

Perfs:

Top	Bot	Thru	Comments
4164	4184		

Remarks: QUALITY WELL SERVICE USING COMMON CEMENT, TICKET #39697, CASING LEAK AT 750', TRIED TO REPLACE CASING NEVER GOT CASING TO SCREW TOGETHER.

Plugged through: CSG

District: 02

Signed B. J. Hope
8/28/12

(TECHNICIAN)

RECEIVED

AUG 16 2012 Form CP-2/3

KCC WICHITA