

To: 1090483 9-30
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-NA5-135-19051-0000
C SE NW 7, SEC. 7, T. 20 S, R 21 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name O'Brien A-P Well # 2

Operator: Ritchie Exploration, Inc.

County Ness

Name & Address 125 N. Market, Ste. 1000
Wichita, KS 67202

Well Total Depth 4372 142.09 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 509

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 30 Month: 9 Year: 19 94

Plugging proposal received from Manny Boatright

(company name) Kelso Casing Publing (phone) 316-938-2943

were: 4 1/2" at 4371' w/100 sx cement, PBTD 4367', Perfs at 4357-64'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1430',

3rd plug pump 45 sx cement at 725',

4th plug pump 50 sx cement at 530', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 30 Month: 9 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped in 85 sx cement at 725',

3rd plug pulled to 525', circulated cement to surface with 115 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 725' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (did / XXXXXX) observe this plugging.

DATE 10-10-94

INV. NO. 41382

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 04 1994

WICHITA, KANSAS