

7-6-88

1 070560

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,925 - ~~0000~~

C SW SW, SEC. 4, T 20 S, R 21 W ~~EX~~

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5303

Lease Name Young Well # 1

Operator: Canady Oil Corporation
Name & Address: 920 North Tyler
Wichita, KS 67212

County Ness 145.02
Well Total Depth 4462 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 520

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address: Box 347, Chase, KS 67524

Company to plug at: Hour: 10:45 a.m. Day: 6 Month: 7 Year: 1988

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4458' PBD 4452' Perfs at 4427-50'

1st plug sand back to 4375' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release wiper plug

and pump 150 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 6 Month: 7 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, released wiper plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 12 1988

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3242' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

Observe this plugging.

INVOICED

Signed Dan Goodrow (TECHNICIAN)

DATE 7-21-88
INV. NO. 21509