

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-20280-00-00  
Spot: W2NWNE Sec/Twnshp/Rge: 35-22S-2W  
660 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: NEUFELD Well #: 1  
County: HARVEY Total Vertical Depth: 2988 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2989	560	125 sxs cmt
SURF	8.625	241		175 sxs cmt

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/09/2012 8:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: TRAVIS HAMM Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS, AS PER THEIR RECOMMENDATIONS.

Plugging Proposal Received By: HUNTER CLARK Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/09/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:  
SANDED BACK TO 2575' - CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 560' PULLED CASING TO 320'. CIRCULATED TO SURFACE WITH 210 SX CEMENT AND 250 LBS OF HULLS.

Perfs:

Top	Bot	Thru	Comments
2985	2988		MISSISSIPPIAN

Remarks: COPELAND CEMENTING OUT OF BURRTON, 60/40/4% POS MIX, TICKET #37971  
Plugged through: CSG

District: 02 Signed BJ Hope (TECHNICIAN)  
8/27/12

RECEIVED Form CP-2/3  
AUG 16 2012  
KCC WICHITA

*Handwritten mark*