

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-26308-00-00  
Spot: E2NWNESW Sec/Twnshp/Rge: 11-15S-19W  
2310 feet from S Section Line, 1920 feet from W Section Line  
Lease Name: BEFORT Well #: 1  
County: ELLIS Total Vertical Depth: 3750 feet

Operator License No.: 4787

Op Name: TDI, INC.

Address: 1310 BISON RD  
HAYS, KS 67601

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
SURF	8.625	211		150 sx

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/12/2012 12:00 AM

Plug Co. License No.: 33350

Plug Co. Name: SOUTHWIND DRILLING, INC.

Proposal Rcvd. from: JERRY

Company: SOUTHWIND DRILLING, INC.

Phone: (620) 617-1716

Proposed Plugging Method: Ordered 230 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE

WitnessType: NONE

Date/Time Plugging Completed: 08/12/2012 9:30 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

1st plug @3650 w/25 sx  
2nd plug @1270 w/25 sx  
3rd plug @545 w/100 sx  
4th plug @260 w/40 sx  
5th plug @40 w/10 sx

Rathole 30 sx

RECEIVED  
AUG 17 2012  
KCC WICHITA

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Bruce Rodie  
8/28/12 (TECHNICIAN)

CM

AUG 13 2012