

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-23,280-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 JAN 31 1989
 01-31-1989
 Wichita, Kansas

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Finnup

WELL NUMBER 1

1650 Ft. from S Section Line

1320 Ft. from E Section Line

SEC 17 TWP. 18 RGE. 25 (X) or (W)

COUNTY Ness

Date Well Completed 11/9/88

Plugging Commenced 11/9/88

Plugging Completed 11/9/88

LEASE OPERATOR Totten Resources, Inc.

ADDRESS 2506 Greenleaf CT, Wichita, KS

PHONE # (316) 687-4959 OPERATORS LICENSE NO. 3567

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/7/88 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Miss Depth to Top 4501 Bottom 4505 T.D. 4560

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss surface	oil & wtr	4501	05	4 1/2	4560	2,105'
		224	sur	8 5/8	224	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. pulled on pipe, parted, pulled 2,105', Ran 50sx @ 1810', 80sx @ 1080', 40sx @ 240' 10sx @ 40', 15sx in RH. Total 195 sx 60/40 poz, 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. _____

Address Ness City, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Totten Resources, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Matt Totten (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]


(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 25 day of Jan, 19 89



Janet S. Silvesthorne
 Notary Public

15-135-23280-00-00



WIRE-TECH

RADIATION GUARD LOG

COMPANY TOTTEN RESOURCES INC.
 WELL FINNUP #1
 FIELD WILD CAT
 COUNTY NESS STATE KANSAS
 Location S1/2 - N1/2- SE Other Services. NONE

Sec. 17 Twp 18S Rge 25W

Permanent Datum GROUND LEVEL Elev 2510 Elev K B 2511'
 Log Measured From KELLY BUSHING 5 FT Ft. Above Perm. Datum DF
 Drilling Measured From KELLY BUSHING G L 2510'

Date 8-23-88
 Run No ONE
 Depth—Driller 4580'
 Depth—Wire-Tech 4562'
 Btm Log Inter 4561'
 Top Log Inter 3500'
 Casing—Driller 224' @ 85/8
 Casing—Wire-Tech
 Bit Size 7 7/8
 Type Fluid in Hole CHLH.
 Dens I Visc 9.5 I 48
 pH I Fluid Loss 9.5 I 12 ml
 Source of Sample MUD PIT
 R_m u Meas Temp .95 @ 76 °F
 R_m u Meas Temp. .684 @ 76 °F
 R_m u Meas Temp 1.33 @ 76 °F
 Source R_m:R_{mc} CHARTS I
 R_m u BHT .62 @ 120 °F
 Time Since Circ 4 HRS.
 Max Rec Temp 120°F @ T.D.
 Equip I Location 60 I GT.
 Recorded By W. CURTIS
 Witnessed By MR. M. TOTTER

RECEIVED
 KANSAS RADIATION COMMISSION
 NOV 7 1988
 CONSERVATION DIVISION
 Wichita, Kansas
 11-07-1988

FIELD PRINT