

15-135-20964-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Ness County. Sec. 17 Twp. 18S Rge. (E) 25 (W)  
Location as "NE/CNW/SW" or footage from lines C/NE SE

Lease Owner Wolland, Inc.  
Lease Name Finnup Well No. 1  
Office Address Box 519, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 21 19 74  
Application for plugging filed November 21 19 74  
Application for plugging approved November 21 19 74  
Plugging commenced November 21 19 74  
Plugging completed November 21 19 74  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4478 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	323'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole plugged as follows: Plugged at 650' with 70 sacks of common cement; plugged at 240' with 20 sacks of common cement & hulls; plugged at 40' with 10 sacks of common cement.  
Plug down at 10:45 A. M. November 21, 1974.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling Company  
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.  
Kenneth J. Link (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link  
Kenneth J. Link  
P. O. Box 355, Great Bend, Kansas 67530  
(Address)

My commission expires \_\_\_\_\_  
Subscribed and sworn to before me this 29th day of November 19 74  
Elnine H. Taylor  
Elnine H. Taylor Notary Public.



D R I L L E R S    L O G

#1 Finnup

CASING:  
317.52' of used 8-5/8"  
surface casing.

COMPANY: Wolland, Inc.  
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C/NE SE  
Section 17-18S-25W  
Ness County, Kansas

TOTAL DEPTH:  
4478'

COMMENCED: November 11, 1974  
COMPLETED: November 21, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock	0	50	Ran 317.52' of used 8-5/8" surface casing; set and cemented at 323' with 200 sacks of common cement, 2% gel and 3% C. C. Plug down at 5:45 A. M. November 12, 1974.
Shale w/Sand Streaks	50	100	
Shale & Shells	100	335	
Shale, Red Bed w/Sand Streaks	335	1020	
Shale	1020	1825	
Shale & Line Streaks	1825	2360	
Lime & Shale	2360	4075	
Lime	4075	4125	
Lime & Shale	4125	4224	
Lime	4224	4350	
Lime & Shale	4350	4478	

ROTARY TOTAL DEPTH: 4478'

D. & A.

Plugged hole as follows: Plugged at 650' with 70 sacks of common cement; plugged at 240' with 20 sacks of common cement & hulls; plugged at 40' with 10 sacks of common cement. Plug down at 10:45 A. M. November 21, 1974.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this 29th day of November, 1974.

My Commission Expires:

December 14, 1977

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JAN 6 1975

CONSERVATION DIVISION  
Wichita, Kansas

01-06-1975