

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
100 Bittling Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Ness County. Sec. 19 Twp. 18 R. 25 (b) (1) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NY NY NE

Lease Owner. **Newton Oil Company**  
Lease Name. **Shiner** Well No. **2**  
Office Address. **910 Equitable Bldg., Denver, Colorado**  
Character of Well (completed as Oil, Gas or Dry Hole)... ~~Oil~~ **Dry H**  
Date well completed... **Sep. 27, 1937** 19... **Hole**  
Application for plugging filed... 19...  
Application for plugging approved... **November 14** 19... **45**  
Plugging commenced... **November 8** 19... **45**  
Plugging completed... **November 8** 19... **45**  
Reason for abandonment of well or producing formation... **Dry Hole**



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production... 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well... **H. W. Kerr, Great Bend, Kans.**  
Producing formation... Depth to top... Bottom... Total Depth of Well **1400** Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|------|--------|------------|
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Cut off 10-3/4" pipe, filled hole with mud.  
Set rock bridge at 500 feet. Filled pipe to 250 feet with surface soil. run 20 sacks cement at 250 feet, filled 10-3/4" surface with surface soil to 20 feet base cellar, cemented surface cap with 10 sacks cement.

JUL 8 - 1947  
07-08-1947

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to **Newton Oil Company**  
Address... **910 Equitable Bldg., Denver, Colorado**

STATE OF... **COLORADO**... CITY AND... COUNTY OF... **DENVER**... ss.  
**H. L. Jewell, Treasurer**... (employee of owner) ~~or contractor~~ of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. L. Jewell*  
**910 Equitable Bldg., Denver 2, Colorado**  
(Address)

SUBSCRIBED AND SWORN to before me this **7th** day of **July** 19 **47**  
*Dorothy A. Lewis*  
Notary Public.

My commission expires... **July 30, 1949**

19 18 25W  
32 45

PLUGGING

FILE SEC... LINE

15-135-19118-00-00

ORIENT L OIL COMPANY

Sec. 19 T. 18 R. 25W  
NW NW NE  
Hess County, Kansas

SHINER # 2

Shut down at 1875 ft.

Commenced Sept. 13, 1937

Shut down Sept. 27, 1937

Casing

10 1/2" 640 ft. 740 sack cement

Rotary Log

|                         |      |
|-------------------------|------|
| Line & Sticky Shale     | 200  |
| Shale                   | 350  |
| Shale & Sand            | 500  |
| " "                     | 650  |
| Red Bed & Shale         | 660  |
| Shale                   | 915  |
| Line & Shale            | 1065 |
| Shale & Sand            | 1200 |
| Shale                   | 1260 |
| Shale & Red Bed         | 1270 |
| Anhydrite               | 1280 |
| Shale & Red Bed         | 1520 |
| Broken Sand             | 1535 |
| Shale                   | 1580 |
| Red Bed                 | 1590 |
| Red Bed, Sand, Red Rock | 1770 |
| Red Bed & Rock          | 1800 |
| Green Shale & Red Rock  | 1815 |
| Red Rock & Shale        | 1875 |

NEWTON OIL COMPANY  
Denver, Colorado

November 11, 1945

Report furnished by Standard Casing Pulling Company of Great Bend, Kansas of plugging work as instructed by State Plugger Mr. Herb Kerr:

Cut off 10-3/4" pipe, filled hole with mud. Set rock bridge @ 500 feet. Filled pipe to 250 feet with surface soil; run 20 sacks cement @ 250 feet, filled 10-3/4" surface with surface soil to 20 feet base cellar, cemented surface cap with 10 sacks cement. Well plugged.

19 18 25W  
22 45

NOV 30 1945  
11-30-1945