


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County, Sec. 25 Twp. 18S Rge. 23 (E) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW&SW&" or footage from lines C SW SE
Lease Owner Rains & Williamson Oil Co.
Lease Name Bondurant Well No. 1
Office Address 412 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-9 1962
Application for plugging filed 10-9 1962
Application for plugging approved 10-9 1962
Plugging commenced 10-9 1962
Plugging completed 10-9 1962
Reason for abandonment of well or producing formation No oil or gas found in commercial quantities
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 600 ft. Cement through D.P. W/20 sacks. Fill hole up to 240' w/ Rotary mud, set Plug and Cement through D. P. W/ 20 sacks. Fill hole up to 35' base of Cellar and Cap W/10 sacks.

[Handwritten signatures and dates]
10-10-1962

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co.
Address 412 Union Center Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wilson Rains - Partner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains - Partner
412 Union Center Building, Wichita,
Kansas

SUBSCRIBED AND SWORN TO before me this 12 day of October, 1962

Sandra Ames
Sandra Ames
Notary Public.

My commission expires August 14, 1966

Operator: Rains & Williamson Oil Co.
No. 1 Bondurant
C SW SE Sec. 25-18S-23W
Ness County, Kansas

Contractor: Rains & Williamson Oil Co.
Comm: 9-27-62
Comp: 10-9-62

Remarks: set 8 5/8" surface casing at
249'. 140 sacks Portland cem.

Formations:

Surface Clay	40'
Sand & Shale	85'
Shale & Shell	250'
Cement	250'
Shale & Sand	300'
Red Bed & Shale	430'
Sand & Shale	750'
Shale & Shell & Red Bed	900'
Anhydrite	930'
Shale & Shell	1080'
Sand	1300'
Shale & Red Bed	1500'
Shale & Red Bed	1555'
Anhydrite	1600'
Shale & Shells	1705' to 2210'
Lime	2270'
Lime & Shale	2400'
Lime & Shale	2350'
Lime	2360'
Lime & Shale	2730'
Lime & Shale	2875' to 3770'
Lime & Shale & Chalk	3825'
Lime	3880'
Lime & Chert	3920'
Lime	3980' to 4405'
Chert	4405'
Chert & Lime	4458'
Rotary Total Depth (D&A)	4458'

RECEIVED
STATE CORPORATE COMMISSION

OCT 13 1962

CONSERVATION DIVISION
Wichita, Kansas

10-10-1962

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO.

By: *Wilson Rains*
Wilson Rains
Partner

Subscribed and sworn to
before me, a Notary Public
in and for the State of Kansas,
County of Sedgewick, this 12
day of October, 1962.

My commission expires:
August 14, 1966
Sandra Ames