

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County, Sec. 32 Twp. 18S Rge. 23W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C SW NW


Lease Owner Beren Corporation  
Lease Name Eibert Well No. #1  
Office Address 970 Fourth Financial Center, Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed December 5, 1980 19  
Application for plugging filed December 5, 1980 19  
Application for plugging approved December 5, 1980 19  
Plugging commenced December 5, 1980 19  
Plugging completed December 5, 1980 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation Depth to top Bottom Total Depth of Well 4325'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows:  
70 sacks @ 840', 20 sacks @ 420', hulls and 10 sacks @ 40', 2 sacks in mousehole, 3 sacks in rathole.  
Plugging completed at 7:30 p.m., December 5, 1980

12-19-1980  
DEC 19 1980  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.  
Charles W. Steincamp (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp  
P. O. Box 355, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1980

Loneita Barry  
Loneita Barry Notary Public.

My commission expires 3-28-84



15-135-21912-00-00

D R I L L E R S    L O G

#1 Eibert

CASING RECORD:  
15 jts. new 23#  
8-5/8" surface  
casing

COMPANY: Beren Corporation  
CONTRACTOR: Strata Drilling Company  
COMMENCED: November 28, 1980  
COMPLETED: December 5, 1980

DESCRIPTION: C SW NW  
Section 32-18S-23W  
Ness County, Kansas

TOTAL ROTARY  
DEPTH: 4325'

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale and lime	0	645	Ran 630' new 23# 8-5/8" surface casing; set and cemented at 635' with 400 sacks 60-40 pozmix, 2% gel, 3% C.C. Cement circulated. Plug down at 5:45 a.m., November 29, 1980.
Shale, sand, shale	645	1498	
Anhydrite	1498	1532	
Shale	1532	2195	
Lime and shale	2195	4210	
Lime	4210	4325	
			Ran 2 drill stem tests.
			Ran 1 electric log.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 840', 20 sacks @ 420', hulls and 10 sacks @ 40', 2 sacks in mousehole, 3 sacks in rathole. Plugging completed at 7:30 p.m., December 3, 1980.

STATE OF KANSAS )  
                          ) ss  
COUNTY OF BARTON)

DEC 19 1980  
12-19-1980  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp  
Charles W. Steincamp

Sworn to and subscribed before me this 15th day of December, 1980.

My appointment expires 3-28-84.

Loneita Barry  
Loneita Barry, Notary Public

