

15-135-21694-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County. Sec. 2 Twp. 18 Rge. 25 E/W  
Location as "NE/CNW/SW" or footage from lines  
150' NW OF NW NW


Lease Owner Walters Drilling Co., Inc.  
Lease Name Moses Estate Well No. 1  
Office Address 400 Insurance Building, Wichita 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed 10/6/79 19  
Application for plugging filed 10/6/79 19  
Application for plugging approved 10/6/79 19  
Plugging commenced 10/6/79 19  
Plugging completed 10/6/79 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well  
Show depth and thickness of all water, oil and gas formations. RTD 4365'



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	453	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 550' with 70 sacks 50/50 Poz, 6% gel  
Middle plug @ 300' with 20 sacks 50/50 Poz, 6% gel  
Top & Bridge plug at 40' with 10 sacks 50/50 Poz 6% gel  
5 sacks in rathole  
Job complete @ 5:15 p.m. 10/6/79

10-18-1979  
10-19-1979  
10-19-1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
James C. Remsberg of Slawson Drilling Company, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

James C. Remsberg  
James C. Remsberg  
200 Douglas Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of October, 1979

Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Walters Drilling Company, Inc.  
 400 Insurance Building  
 Wichita, Kansas 67202

LEASE: Moses Estate #2  
 150' NW of NW NW Sec. 2-18S-25W  
 Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
 200 Douglas Building  
 Wichita, Kansas 67202

COMMENCED: 9/29/79

COMPLETED: 10/6/79

RTD: 4365'

SURFACE CASING: 8-5/8" set at 453' with 290 sx cm

0' to 458' Clay, Sand & Shale (458' 12½" Surface Hole)  
 458' to 540' Shale & Sand  
 540' to 1500' Shale, Shells, & Sand  
 1500' to 1620' Shale & Sand  
 1619' to 1652' Anhydrite  
 1652' to 1870' Sand & Shale  
 1870' to 2350' Shale & Sand  
 2350' to 2525' Shale & Shells  
 2525' to 2765' Shale & Lime  
 2765' to 4005' Lime & Shale  
 4005' to 4120' Lime  
 4120' to 4190' Lime & Shale  
 4190' to 4270' Lime  
 4270' to 4330' Lime & Shale  
 4330' to 4365' Lime  
 4365' RTD

RECORDED  
 OCT 18 1979

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the Moses Estate #2 log for Walters Drilling Company, Inc.

*James C. Remsberg*

Subscribed and sworn to me this  
 15th day of October 1979

*Mary Lou Taylor*  
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

