


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 2 Twp. 18S Rge. 25WE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW/4 NE/4

Lease Owner Walters Drilling Company
Lease Name MOSES ESTATE Well No. 1
Office Address 400 Insurance Building, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed June 9 1979
Application for plugging filed (verbally) June 9 1979
Application for plugging approved (verbally) June 9 1979
Plugging commenced June 9 1979
Plugging completed June 9 1979

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4394'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4394'

Set 1st plug at 630' with 50 sacks
2nd plug at 430' with 40 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 3 sacks.

Cemented with 50/50 posmix, 6% gel.
Plug was down at 11:45 a.m., 6-09-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner, or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1979



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

15-135-21632-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Walters Drilling Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Moses Estate #1
LOCATION:	C SW/4 NE/4, Section 2-18S-25W Ness County, Kansas
SPUD DATE:	May 29, 1979
COMPLETION DATE:	June 9, 1979

0	391	Sand and shale
391	1410	Shale
1410	1995	Sand and shale
1995	3655	Shale
3655	3683	Sand
3683	4018	Shale and lime
4018	4372	Lime
4372	4394	Shale
	4394	Rotary Total Depth

Spud hole at 11:45 p.m., May 29, 1979. Drilled 452' of 12 1/4" hole. Ran 15 joints of 8-5/8" - 24# casing. Set at 449' K.B. with 250 sacks of Class A cement, 3% Ca.Cl., 2% gel. Cement did circulate. Pumped plug to 430' K.B. Plug was down at 12:30 p.m., May 30, 1979.

T.D. 4394'. Set 1st plug at 630' with 50 sacks, 2nd plug at 430' with 40 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 3 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 11:45 a.m., June 09, 1979.

SAMPLE TOPS:

Anhydrite 1621'
B/Anhydrite 1657'

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

RECEIVED
06-15-1979

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Moses Estate #1, C SW/4 NE/4, Section 2-18S-25W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 13th day of June, 1979.



Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 8-21-82.