

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Ness County, Sec. 6 Twp. 18 Rge. (E) 25 (W)

NORTH


Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner The Bay Petroleum Corporation  
Lease Name Dinges 'B' Well No. 1  
Office Address Box 957 Denver Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 20 19 52  
Application for plugging filed July 2 19 52  
Application for plugging approved July 3 19 52  
Plugging commenced June 26 19 52  
Plugging completed July 17 19 52  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Stough  
Producing formation Mississippi Depth to top 4364 Bottom 4390 Total Depth of Well 4390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	297'	None
				5 1/2"	4370'	3659'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with rock from 4390' to 4350'  
Dumped 5 sacks cement at 4350'  
Mudded hole to 297'  
Set bridge at 297' and ran 20 sacks cement  
Mudded hole and ran 10 sacks cement to  
bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Standard Pulling Co.  
Address Lyons Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Glen E. Armour (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 1 day of August 19 52

My commission expires May 20 1954

Quintus Gray  
Notary Public.

24-2675-S 2-52-20M  
REC. SEC. 6 TWP. 18 R. 25 W.  
PAGE 27 LINE 45  
08-02-1952

15-135 (1583-00-00)

COMPANY: BAY PETROLEUM CORPORATION Rotary Drilling Commenced: 5-31-52  
 Denver, Colorado Rotary Drilling Completed: 6-15-52

LOCATION: DINGES B-1  
 SE SE SE 6-18S-25W  
 Ness County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY  
 Wichita, Kansas

CASING RECORD: 297' 8 5/8" 2 1/4" O.D. surface casing set at 297' in a 12 1/4" hole,  
 cemented with 175 sacks cement.

4372' (176 jts.) 5 1/2" O.D. casing set at 4372' in a 7 7/8" hole,  
 cemented with 75 sacks cement.

LOG

(Figures indicate bottom formation - measurements from top rotary bushing.)

Clay	30	Circulate for samples at 4300'.
Gravel	40	" " " " 4349'.
Shale	297	" " " " 4363'.
Shale & Shells	435	" " " " 4365'.
Sand	520	" " " " 4371'.
Shale & Streaks of Pyrite	810	" " " " 4374'.
Shale, Red Bed & Stks of Sand & Shells	1125	" " " " 4377'.
Anhydrite	1160	" " " " 4382'.
Shale, Shells & Sand	1225	" " " " 4387'.
Sand	1460	" " " " 4392'.
Shale & Stks. Sand	1740	Slope test at 1000' - 0° off.
Shale, Shells & Streaks of Red Bed	1995	Slope test at 2,000' - 0° off.
Shale	2170	Slope test at 3,000' - 0° off.
Shale & Shells	2660	SLM at 3,000' - O.K.
Lime & Shale	2730	Slope test at 4392' - 0° off.
Lime, Shale & Stks. of hard Sand	2765	SLM at 4392' - O.K.
Lime	2826	Circulation lost at 3012', 3014', 3020'.
Lime & Shale	3215	
Shale & Shells	3426	
Shale	3580	
Lime & Shale	3713	
Lime	4130	
Lime & Shale	4190	
Lime	4245	
Lime & Shale	4345	
Lime	4365	
Cherty Lime	4377	
Lime	4382	
Cherty Lime	4387	
Lime	4392 T.D.	

The undersigned, C. W. Sebitts, Attorney-in-fact of PICKRELL DRILLING COMPANY, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PLUGGING

FILE SEC 6-T-18-25W  
BOOK PAGE 27 LINE 45

PICKRELL DRILLING COMPANY  
By C. W. Sebitts  
Attorney-in-fact.

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS

08-02-1952

On this 1st day of July, 1952, before me the undersigned, a Notary Public in and for the County and State aforesaid personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of Pickrell Drilling Company to the foregoing instrument as its Attorney-in-fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.  
Ethel Zimmerman  
Notary Public

My commission expires January 28, 1953.