

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 - 135 - 22,693-

LEASE NAME Moses Est. "A" ^{CP-00}

WELL NUMBER 1

SPOT LOCATION NE NW NE

SEC. 10 TWP. 18S RGE. 25 ~~XXXX~~ (W)

COUNTY Ness

Date Well Completed 10-15-84

Plugging Commenced 5:30 PM,
10-15-84

Plugging Completed 7:00 PM,
10-15-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Walter Oil and Gas Corporation
ADDRESS 240 Main Building, 1212 Main Street
Houston, Texas 77002

PHONE # (713) 659-1221 OPERATORS LICENSE NO. 9289

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4370'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 308' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud. Plugged with 50 sacks at 1640';
40 sacks at 720'; 50 sacks at 350' 1/2 sack bulls, Hawco plug ant 10 sacks
at 40'. 15 sacks in rathole. Used 60/40 Pozmix, 2% gel and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.


F. A. Wuellner (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

STERLING DRILLING COMPANY
(Signature) [Signature]
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Kansas
67579

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 84.

[Signature]
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-85



15-135-22693-00-00

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - MOSES EST. "A" #1
Located: NE NW NE, Section 10-18S-25W, Ness County, Kansas

OWNER: Walter Oil and Gas Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 9, 1984
COMPLETED: October 15, 1984

TOTAL DEPTH: 4370'

| <u>LOG</u> | <u>CASING RECORD</u> |
|----------------------------|---------------------------------------|
| 0 - 285 Clay and Shale | Ran 7 joints 8 5/8" casing. 295.47' |
| 285 - 310 Shale | pipe set at 308' K.B. Cemented with |
| 310 - 1230 Clay, Shale | 200 sacks 60/40 Pozmix, 2% gel and |
| 1230 - 1645 Shale | 3% cc. Plug down at 5:30 PM, 10-9-84, |
| 1645 - 1664 Anhydrite | by Howco. |
| 1664 - 4370 Lime and Shale | Plugged. |

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1984

CONSERVATION DIVISION
Wichita, Kansas

10-26-1984

Deviation Surveys: 1° at 1740'
1° at 4370'