

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-135-22,628-0-00

LEASE NAME Moses Estate Trust

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 1

SPOT LOCATION C/NW/NW

LEASE OPERATOR Walter Oil & Gas Corporation

SEC. 11 TWP. 18 SRGE. 25 (E) OR (W)

ADDRESS 240 Main Bldg., 1212 Main St., Houston, Texas 77002

COUNTY Ness

PHONE #(713) 659-1221 OPERATORS LICENSE NO. 9289

DATE WELL COMPLETED 9/5/84

CHARACTER OF WELL D&A  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 9/12/84

PLUGGING COMPLETED 9/12/84

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District One

Is ACC-1 FILED? No IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION N/A DEPTH TO TOP \_\_\_\_\_ BOTTOM T.D. 4305'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Marmaton	salt water	3704'	3707'	8-5/8"	269' KB	None
Mississippi	salt water	4296'	4306'	4-1/2"	4296' KB	None

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.  
Halliburton pumped 1 sx cottonseed hulls on bottom; 10 sx cement 4300'-4100'; 15 sx gel 4100'-1600'; 20 sx cement 1600'-1300'; 5 sx gel 1300'-1000'; 70 sx cement 1000'-surface; plug down @ 4:15 p.m. 9/12/84

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Hembree Well Service LICENSE No. 960  
ADDRESS P. O. Box 458, Ness City, Kansas 67560

STATE OF TEXAS COUNTY OF HARRIS, SS.

KIM BURKETT (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

OCT 09 1984  
CONSERVATION DIVISION  
WICHITA, KANSAS

10-09-1984

(SIGNATURE) Kim Burkett  
(ADDRESS) 240 Main Bldg., 1212 Main St. Houston, Texas 77002

SUBSCRIBED AND SWORN TO BEFORE ME THIS SUNDAY OF OCTOBER 1984

Janice R. Webb  
NOTARY PUBLIC  
Notary Public - State Of Texas  
My Commission Expires 12-30-87

MY COMMISSION EXPIRES: 12-30-87

# STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

15-135-22628-00-00

WELL LOG ----- MOSES EST. TRUST #1  
Located: C NW NW, Section 11-18S-25W, Ness County, Kansas

OWNER: Walter Oil and Gas, Inc.

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 18, 1984

COMPLETED: August 26, 1984

TOTAL DEPTH: 4305'

## LOG

0 - 130 Gravel and Clay  
130 - 270 Shale  
270 - 1602 Shale and Lime  
1602 - 1615 Anhydrite  
1615 - 1621 Anhydrite - Lime  
1621 - 4305 Lime and Shale

## CASING RECORD

Ran 6 joints 8 5/8" casing. 255.59' pipe set at 269' K.B. Cemented with 185 sacks Common, 3% cc. Plug down at 7:00 PM, 8-18-84, by Howco.

Ran 102 joints 4 1/2" casing. 4294.99' pipe set at 4296' K.B. Cemented with 600 sacks Howco Lite, 10# gilsonite per sack, 140 sacks 60/40 Pozmix, 2% gel, 10% salt. Plug down at 11:20 AM, 8-26-84, by Howco.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1984

CONSERVATION DIVISION  
Wichita, Kansas

10-26-1984

Deviation Surveys: 1° at 1850'  
3/4° at 4305'